





Workshop on Ocean Thermal Energy Conversion (OTEC):
Assessing Potential Physical, Chemical and Biological Impacts
and Risks


June 22, 2010











Gross Power vs Net Power



- Gross Power 14.44 MW =>Avg. Net Power: 10 MW
- Key Parasitic Loads
 - CW Pumps: 2.24 MW
 - WW Pumps: 1.31 MW
 - Ammonia Pumping: 0.18 MW
 - Topsides Load: 0.4 MW

Typical Component Efficiencies

Turbo-generator: 80%

Power Cable: 97%

Seawater Pumps: 75%

Power Cable: Variable 94%-97%

Transformers: Variable 98%-99%

10 MWnet Pilot Plant


14.4 MWgross power

WW inlet at 20m deep Screen velocity = 0.15m/s

CW intake at 1000m deep, ~100m above seabed

CWP velocity = 2.5m/s

Two discharges at 70 – 90m (TBR) depth with 1 m/s downward velocity



Flow Summary 100 MWnet


~140 MWgross power

WW inlet at 20-30m deep Screen velocity = 0.15m/s


CW intake at 1000 - 1200m deep


Intake ~100m above seabed

Discharges at 70 – 90m (TBR) depth



What's in a Remora?






Evaporators




- 6 identical "batteries" per Remora
- A3003 brazed aluminum
- Biofouling controlled via hypochlorite treatment
 - Periodic 1 hour per day
 - Concentration 70ppb
- Water Flow: 23 tonne/s
- Heat Transfer area: 17111 m²



Condensers

Two 4.3m dia x 7m tall Shell & Tube HX per Remora





Material: Titanium (pending more corrosion test data for Al alloys)

Form Factor: Enhanced Tubes (either

twisted or spirally indented)

Heat Transfer Area: 22407 m2

Water Flow: 18.3 tonne/s

Biofouling control: N/A




Tube support baffles are not required, making compact design

Swirling Flow Enhances
Heat Transfer
Coefficient on Both
Sides without
Corresponding Increase
in Pressure Drop

Seawater Pumps







2/16/10 0930

Ammonia System



- Minimal valves in seawater
- Redundant pumps within sealed pods
- Full system "charge" approximately 16,000 gallons (10MW plant) NH3





Platform: Moored Platform Installed Using ABS and/or DNV Standards



